



Procurement Department

Mrs. Geri Sams, Director

MAILED: EMAIL/CERTIFIED

TO: All Vendors
Tywana Scott, Quality Assurance Analyst
Hameed Malik, Engineering and Environmental Services Department

FROM: Geri A. Sams *GASams*
Procurement Director

DATE: January 23, 2023

SUBJ: Revisions - Section 3: Bid Proposal

BID ITEM: Bid Item # 22-303 Wrightsboro Rd Reconstruction and Pedestrian Improvements (Marks Church Road to Highland Avenue) for Augusta, GA – Engineering and Environmental Services Department

BID OPENING DATE: Wednesday, February 1, 2023 @ 3:00 p.m.

ADDENDUM NO. 4

This Addendum shall form a part of the referenced Bid Item #22-303 Wrightsboro Road Reconstruction and Pedestrian Improvements (Marks Church Road to Highland Avenue) and any agreement entered in connection therewith equally as if bound into the original document. Acknowledge receipt of all Addendums on Attachment "B" within the Specifications package.

Responses to Vendor's Questions:

- Please see the Revised Bid Proposal attached to this Addendum 4.

Please acknowledge addendum in your submittal

END OF ADDENDUM

Attachments: Revised Bid Proposal (6 Pages)

Room 605 - 535 Telfair Street, Augusta Georgia 30901
(706) 821-2422 - Fax (706) 821-2811

www.augustaga.gov

Register at www.demandstar.com/supplier for automatic bid notification



Scan this QR code with your smartphone or camera equipped tablet to visit the Augusta, Georgia

**AUGUSTA ENGINEERING DEPARTMENT
WRIGHTSBORO RD RECONSTRUCTION AND PEDESTRIAN IMPROVEMENTS
(MARKS CHURCH RD TO HIGHLAND AVE)**

SECTION 3: BID PROPOSAL

Date: _____

Gentlemen:

In compliance with your invitation for bids dated _____, 2023, the undersigned hereby proposed to furnish all labor, equipment, and materials, and to perform all work for the installation of roadway improvements, and appurtenances referred to herein as:

**WRIGHTSBORO RD RECONSTRUCTION AND PEDESTRIAN
IMPROVEMENTS (MARKS CHURCH RD TO HIGHLAND AVE)**

In strict accordance with the Contract Documents and in consideration of the amounts shown on the Bid Schedule attached hereto and totaling:

_____ DOLLARS
(\$ _____)

The undersigned hereby agrees that, upon written acceptance of this bid, he will within 10 days of receipt of such notice execute a formal contract agreement with the OWNER, and that he will provide the bond or guarantees required by the Contract Documents.

The undersigned hereby agrees that, if awarded the contract, he will commence the work within 10 calendar days after the date of written notice to proceed, and that he will complete all work within 540 calendar days.

The undersigned acknowledges receipt of the following addenda:

Addendum Number:

Addendum Date:

Respectfully submitted:

(Name of the Firm)

(Business Address)

By: _____

Title: _____

**AUGUSTA ENGINEERING DEPARTMENT
WRIGHTSBORO RD RECONSTRUCTION AND PEDESTRIAN IMPROVEMENTS
(MARKS CHURCH RD TO HIGHLAND AVE)**

ROADWAY					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
000-1000	Force Account	LS	LS	\$ 500,000	\$ 500,000
150-1000	TRAFFIC CONTROL -	LS	LUMP		
210-0100	GRADING COMPLETE -	LS	LUMP		
310-1101	GR AGGR BASE CRS, INCL MATL	TN	387		
318-3000	AGGR SURF CRS	TN	2668		
402-1801	RECYCLED ASPH CONCPATCHING, INCL BITUM MATL	TN	1665		
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	100		
402-4510	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	6458		
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	10334		
413-0750	TACK COAT	GL	9215		
432-0216	MILL ASPH CONC PVMT, 4 IN DEPTH	SY	77285		
432-0206	MILL ASPH CONC PVMT, 1 ½ IN DEPTH	SY	667		
441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	14		
441-0018	DRIVEWAY CONCRETE, 8 IN TK	SY	2168		
441-0104	CONC SIDEWALK, 4 IN	SY	10697		
441-0108	CONC SIDEWALK, 8 IN	SY	1985		
441-0748	CONCRETE MEDIAN, 6 IN	SY	53		
441-4040	CONC VALLEY GUTTER WITH CURB, 6 IN	SY	378		
441-4050	CONC VALLEY GUTTER WITH CURB, 8 IN	SY	456		
441-5002	CONCRETE HEADER CURB, 6 IN, TP 2	LF	605		
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	678		
444-1000	SAWED JOINTS IN EXIST PAVEMENTS - PCC	LF	340		
500-3107	CLASS A CONCRETE, RETAINING WALL	CY	42		
500-3201	CLASS B CONCRETE, RETAINING WALL	CY	55		
500-9999	CLASS B CONC, BASE OR PVMT WIDENING	CY	12		

**AUGUSTA ENGINEERING DEPARTMENT
 WRIGHTSBORO RD RECONSTRUCTION AND PEDESTRIAN IMPROVEMENTS
 (MARKS CHURCH RD TO HIGHLAND AVE)**

511-1000	BAR REINF STEEL	LB	809		
515-2020	GALV STEEL PIPE HANDRAIL, 2 IN, ROUND	LF	96		
530-0105	WATERPROOFING	SY	14		
611-3010	RECONSTR DROP INLET, GROUP 1	EA	1		
611-8000	ADJUST CATCH BASIN TO GRADE	EA	113		
611-8050	ADJUST MANHOLE TO GRADE	EA	12		
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4		
634-1200	RIGHT OF WAY MARKERS	EA	21		
EROSION CONTROL					
700-7000	AGRICULTURAL LIME	TN	6		
700-8000	FERTILIZER MIXED GRADE	TN	3		
700-8100	FERTILIZER NITROGEN CONTENT	LB	100		
716-2000	EROSION CONTROL MATS, SLOPES	SY	2500		
TEMPORARY EROSION CONTROL					
163-0232	TEMPORARY GRASSING	AC	2		
163-0240	MULCH	TN	77		
163-0301	CONSTRUCT & REMOVE CONSTRUCTION EXITS	EA	1		
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	134		
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	7200		
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	1		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	134		
165-0310	MAINTENANCE OF CONSTRUCTION EXIT TIRE WASH AREA (PER EACH)	EA	1		
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	14300		
SIGNING AND MARKING					
611-5551	RESET SIGN	EA	51		
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	22		
636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	SF	197		
636-2070	GALV STEEL POSTS, TP 7	LF	141		
636-2080	GALV STEEL POSTS, TP 8	LF	131		

**AUGUSTA ENGINEERING DEPARTMENT
WRIGHTSBORO RD RECONSTRUCTION AND PEDESTRIAN IMPROVEMENTS
(MARKS CHURCH RD TO HIGHLAND AVE)**

653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	95		
653-0130	THERMOPLASTIC PVMT MARKING, ARROW, TP 3	EA	2		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	25421		
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	21452		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	727		
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	16356		
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	18609		
653-3502	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, YELLOW	GLF	15576		
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	300		
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	110		
654-1001	RAISED PVMT MARKERS TP 1	EA	1568		
654-1003	RAISED PVMT MARKERS TP 3	EA	2512		
SIGNALS					
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 1	EA	1		
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 2	EA	1		
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 3	EA	1		
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 4	EA	1		
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 5	EA	1		
615-1100	DIRECTIONAL BORE PIPE – 5 IN	LF	1203		
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	5040		
639-3014	STEEL STRAIN POLE, TP IV - WITH 35 FT MAST ARM	EA	3		
639-3014	STEEL STRAIN POLE, TP IV - WITH 40 FT MAST ARM	EA	1		
639-3014	STEEL STRAIN POLE, TP IV - WITH 45 FT MAST ARM	EA	2		
639-3014	STEEL STRAIN POLE, TP IV - WITH 50 FT MAST ARM	EA	2		
639-3014	STEEL STRAIN POLE, TP IV - WITH 55 FT MAST ARM	EA	6		
639-3014	STEEL STRAIN POLE, TP IV - WITH 35 FT & 55 FT MAST ARM	EA	1		
639-3014	STEEL STRAIN POLE, TP IV - WITH 55 FT & 65 FT MAST ARM	EA	1		
939-5010	ELECTRICAL POWER SERVICE ASSEMBLY, AERIAL SERVICE POINT	EA	5		

**AUGUSTA ENGINEERING DEPARTMENT
 WRIGHTSBORO RD RECONSTRUCTION AND PEDESTRIAN IMPROVEMENTS
 (MARKS CHURCH RD TO HIGHLAND AVE)**

937-6050	INTERSECTION VIDEO DETECTION SYSTEM ASSEMBLY, TYPE A	EA	5		
937-6100	OUTPUT EXPANSION MODULE, TYPE A	EA	5		
936-1010	CCTV SYSTEM, TYPE H	EA	5		
647-3000	INTERNALLY ILLUMINATED STREET SIGN	EA	12		
647-3100	INTERNALLY ILLUMINATED STREET NAME SIGN CONTROL ASSEMBLY	EA	12		
				SUB-TOTAL ROADWAY:	
LIGHTING					
680-4110	LIGHTING (LED LUMINAIRE & POLE)	EA	389		
999-0014	LUMINAIRE AND POLE INSTALLATION	EA	389		
LANDSCAPE					
999-2015	PERSIAN PARROTIA	EA	4		
702-1081	PRINCETON AMERICAN ELM	EA	4		
702-0006	ROSE CREEK ABELIA	EA	82		
999-2015	CINNAMON GIRL DISTYLUM	EA	373		
702-0280	AUGUST BEAUTY GARDENIA	EA	28		
999-2015	DWARF BURFORD HOLLY (TREE FORM)	EA	23		
702-0610	JAZZ HANDS DWARF PINK LOROPETALUM	EA	706		
999-2015	ADAGIO EULALIA GRASS	EA	238		
702-0719	HEAVY METAL SWITCH GRASS	EA	504		
702-0981	LEMON DRIFT ROSE	EA	296		
702-0063	ORANGE DAYLILY	EA	471		
702-0330	STELLA DE ORO DAYLILY	EA	1408		
702-0727	CREEPING PHLOX	EA	321		
700-9300	SOD (HYBRID BERMUDA SOD)	SY	2691		
700-6910	PERMANENT GRASSING (HYBRID BERMUDA SEED)	AC	1.36		
766-7020	IRRIGATION	SF	65817		
702-9025	LANDSCAPING MULCH	SY	3483		
708-1000	PLANTING SOIL MIX	CY	777		
				WTD AVG TOTAL:	

**AUGUSTA ENGINEERING DEPARTMENT
WRIGHTSBORO RD RECONSTRUCTION AND PEDESTRIAN IMPROVEMENTS
(MARKS CHURCH RD TO HIGHLAND AVE)**

Bid Proposal:

GRAND TOTAL

----- DOLLARS

***GRADING COMPLETE:** *Shall include any work without a specific pay item such as:* removal and disposal of all miscellaneous roadway items, utility items, and drainage items (i.e. demolition items). Additional items shall be included in the item of grading complete, unless otherwise established as separate contract items, including, but not limited to: removal/demolition of pavement, removal/demolition of concrete sidewalks and driveways / valley gutter, removal of curb and gutter, removal of abandoned drainage structures, removal of street signs, and any other miscellaneous removal items whether shown on the plans or not. The items of grading complete shall also include other miscellaneous items of construction not otherwise shown as a separate pay item such as fine grading, general clearing, cut and fill, constructing shoulder and subgrade, finish grading, construction layout, the hauling and disposal of undesirable or surplus materials, removing and/or resetting mailboxes, removing and/or resetting gates and fences, removing and/or resetting irrigation sprinkler heads, bonds and insurance etc. Remove/reconnect water services, reconnect sanitary services, remove/reset signs (type varies), remove/reset water sprinkler systems(complete), remove/reset water valves(size varies), remove/reset yard lamps (type varies) shall be included in grading complete where no separate bid item is established.

****LS (LUMP SUM)** – For all Lump Sum items, attach itemized break of lump sum amount on separate sheet