



VICINITY MAP
N.T.S.



LOCATION MAP - HICKS WATER PLANT RESERVOIR "A"
N.T.S.



LOCATION MAP - HIGHLAND AVENUE PLANT RESERVOIR "A"
N.T.S.

CONSTRUCTION PLANS FOR

N. MAX HICKS WATER PLANT RESERVOIR DAM IMPROVEMENTS (A)

AND


HIGHLAND AVENUE WATER TREATMENT PLANT RESERVOIR DAM #1 EAST & DAM #2 WEST IMPROVEMENTS (B)

PREPARED FOR

BOARD OF COMMISSIONERS OF AUGUSTA, GEORGIA

535 TELFAIR STREET, SUITE 220
AUGUSTA, GA 30901

PREPARED BY



CRANSTON

MAY 25, 2023

RECEIVED

AUG 08 2025

Georgia Environmental Protection Division
Watershed Protection Branch

Sheet Index	
Sheet Number	Sheet Title
01	Cover
02	Legend & Notes
03	Overall Existing Conditions
04	Site Plan
05	Erosion Control Notes
06	Erosion Control Notes
07	Erosion Control Notes
08	Initial Erosion Control Plan
09	Intermediate Erosion Control Plan
10	Final Erosion Control Plan
11	Erosion Control Details
12	Miscellaneous Details

Sheet Index	
Sheet Number	Sheet Title
C100	Cover
C200	Notes
C300	Site Plan
C400	Sections
C401	Sections & Details
C600	Erosion Control Notes
C601	Erosion Control Notes
C602	Erosion Control Notes
C603	Initial Erosion Control Plan
C604	Intermediate Erosion Control Plan
C605	Final Erosion Control Plan
C606	Erosion Control Details

MAYOR

GARNETT L. JOHNSON

BOARD OF COMMISSIONERS

DISTRICT 1
JORDAN JOHNSON

DISTRICT 2
STACY PULLIAM

DISTRICT 3
CATHERINE SMITH-RICE

DISTRICT 4
ALVIN MASON

DISTRICT 5
DON CLARK

DISTRICT 6
TONY LEWIS

DISTRICT 7
TINA SLENDAL

DISTRICT 8
BRANDON GARRETT

DISTRICT 9
FRANCINE SCOTT

DISTRICT 10
WAYNE GUILFOYLE

DIRECTOR OF AUGUSTA UTILITIES DEPARTMENT

WES BYNE, P.E.




REV #	DATE	DESCRIPTION
A0	5/25/2023	HICKS PLANS RENUMBERING
B0	5/25/2023	HIGHLAND PLANS RENUMBERING
1	7/28/2025	COMMISSIONERS



2018-0102

C000





VICINITY MAP
N.T.S.

Sheet Index		
Sheet Number	Sheet Title	
01	Cover	
02	Legend & Notes	
03	Overall Existing Conditions	
04	Site Plan	
05	Erosion Control Notes	
06	Erosion Control Notes	
07	Erosion Control Notes	
08	Initial Erosion Control Plan	
09	Intermediate Erosion Control Plan	
10	Final Erosion Control Plan	
11	Erosion Control Details	
12	Miscellaneous Details	

CONSTRUCTION PLANS FOR N. Max Hicks Water Plant Reservoir Dam Improvements

PREPARED FOR
BOARD OF COMMISSIONERS OF AUGUSTA, GEORGIA

535 TELFAIR STREET, SUITE 220
AUGUSTA, GA 30901




LOCATION MAP
N.T.S.

PROJECT DATA:

1. ACREAGE OF PROPERTY: 188.5 ACRES
2. ACREAGE OF DEVELOPMENT: 10.83 ACRES
3. OWNER/DEVELOPER:
BOARD OF COMMISSIONERS OF AUGUSTA, GEORGIA
C/O AUGUSTA UTILITIES DEPARTMENT
452 WALKER STREET, SUITE 200
AUGUSTA GA, 30901
PHONE: 706-312-4153 (DAY); 843-364-0321 (NIGHT)
24 HOUR CONTACT:
NAME: AUD DISPATCH
PHONE: 706-842-3060
4. TAX MAP & PARCEL NUMBERS: 157-0-018-08-0
5. ZONING: SPECIAL EXCEPTION
6. STORM WATER OUTFALL: ---
7. DRAINAGE AREA THIS PROJECT:
3.36 ACRES - A
2.03 ACRES - B
8. IMPERVIOUS AREA:
EXISTING: 0.00 ACRES
PROPOSED: 0.00 ACRES
9. PERVIOUS AREA:
(DISTURBED) EXISTING: 5.39 ACRES
PROPOSED: 5.39 ACRES
UNNAMED TRIBUTARY TO BUTLER CREEK
10. RECEIVING STREAM: SAVANNAH RIVER
11. ULTIMATE STREAM: INDUSTRIAL
12. EXISTING LAND USE: INDUSTRIAL
13. PROPOSED LAND USE: INDUSTRIAL
14. DAM HEIGHT: EXISTING: 31 FEET
9.00 ACRES
15. DAM DRAINAGE BASIN: EXISTING MAX: 96.26 ACRE-FEET
16. LAKE IMPOUNDMENT: EXISTING NORMAL: 7.4 ACRES
10.83 ACRES
17. LAKE SURFACE AREA: 2.37 ACRES-A
2.03 ACRES-B
18. PROJECT AREA: 1
MEDIUM
19. DRAINAGE BASIN AREA: 121-040-05493
GA 05485
20. DAM CATEGORY:
21. DAM SIZE:
22. GEORGIA DAM IDENTIFICATION
23. NATIONAL DAM INVENTORY

PREPARED BY



CRANSTON

APRIL 26, 2019
REV. MAY 25, 2023

BENCHMARK DATA

NAME	DESCRIPTION	PT #	NORTHING	EASTING	ELEVATION
BM-1	TOP OF IRON IN SURVEY MOVEMENT	100001	1226908.71	708604.18	324.80 (NAVD88)
CP-2	TOP OF IRON IN SURVEY MOVEMENT	100002	1226707.41	708594.59	-
CP-3	TOP OF IRON IN SURVEY MOVEMENT	100003	1226649.90	708394.87	-

STORM WATER QUALITY TABLE

ID #	STRUCTURE #/LOCATION	TYPE OF FEATURE	MANUFACTURER/MODEL #	SHEET #
1	N/A	STORMWATER POND	N/A	10
2	N/A	PERMEABLE PAVEMENT SWALE	N/A	10

STORMWATER QUALITY SYMBOL AT EACH FEATURE ON SITE PLAN
WHICH CORRESPONDS TO THE ITEM ON THE CHART.

TOTAL WATER QUALITY VOLUME REQUIRED 766.40 CF
TOTAL WATER QUALITY VOLUME PROVIDED 910.10 CF


REV #	DATE	DESCRIPTION
1	2/20/20	PER SAFE DAM COMMENTS
2	5/25/23	PREPARE FOR BIDDING



G:\PROJECTS\2018\2018-0102 - HICKS WATER PLANT DAM IMPROVEMENTS\AC-DRAWINGS\CIVIL\20180102.DWG 5/31/2023 2:28 PM

GENERAL NOTES:


1. ALL WORK TO BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE STANDARD SPECIFICATIONS OF THE AUGUSTA UTILITIES DEPARTMENT, AND THE PROJECT SPECIFICATIONS.
2. COORDINATE ROAD CLOSINGS AND DETOURS WITH THE AUGUSTA-RICHMOND COUNTY PUBLIC WORKS & ENGINEERING DEPARTMENT (706) 821-1706.
3. CERTIFIED FLAGGERS AND/OR ARROW BOARDS WILL BE REQUIRED TO MAINTAIN TRAFFIC CONTROL WHILE WORKING WITHIN THE LIMITS OF PUBLIC OR PRIVATE ROADWAYS.
4. DATE OF SURVEY - DATA OBTAINED FROM ORIGINAL CONSTRUCTION PLANS; BENCHMARK ELEVATION FIELD SURVEYED BY CRANSTON ENGINEERING ON AUGUST 21, 2018.
5. THE DATA, TOGETHER WITH ALL OTHER INFORMATION SHOWN ON THESE PLANS, OR INDICATED IN ANY WAY THEREBY, WHETHER BY DRAWINGS OR NOTES OR ANY OTHER MANNER, ARE BASED UPON FIELD INVESTIGATIONS AND ARE BELIEVED TO BE INDICATIVE OF ACTUAL CONDITIONS. HOWEVER, THE SAME ARE SHOWN AS INFORMATION ONLY AND ARE NOT GUARANTEED.
6. THE CONTRACTOR WILL IMMEDIATELY NOTIFY THE OWNER IN THE EVENT THAT PREVIOUSLY UNKNOWN HISTORICAL OR ARCHEOLOGICAL SITES ARE DISCOVERED DURING CONSTRUCTION. NO ADDITIONAL WORK IN SUCH AREAS WILL BE ALLOWED UNTIL AUTHORIZED.
7. ALL STRUCTURES, TREES AND SHRUBS WHICH ARE WITHIN THE DESIGNATED CONSTRUCTION AREA, BUT OUTSIDE THE LIMITS OF CONSTRUCTION SHALL NOT BE DISTURBED UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER.
7. CONTRACTOR IS TO CLEAN ALL STORM WATER INLETS AND PIPE AT THE COMPLETION OF CONSTRUCTION TO REMOVE ANY SILT AND DEBRIS. THE CLEANING OF DROP INLETS, CULVERTS, AND PIPES (EXISTING AND PROPOSED) SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT, NO ADDITIONAL PAYMENT WILL BE MADE THEREFOR.
8. UNSUITABLE AND SURPLUS EXCAVATION MATERIAL NOT REQUIRED FOR FILL MAY BE DISPOSED IN ONSITE WASTE OR SPOIL AREAS. CONTRACTOR TO OBTAIN APPROVAL OF ENGINEER FOR EXACT WASTE DISPOSAL AREA.
9. DISTURBANCES TO ANY SURVEY MARKERS OR MONUMENTS REQUIRES RE-ESTABLISHMENT BY A LICENSED SURVEYOR AT THE CONTRACTOR'S EXPENSE.
10. ANY DISCREPANCIES, ERRORS, OR OMISSIONS DISCOVERED ON THE PLANS OR IN THE SPECIFICATIONS SHOULD BE NOTED ON THE CONTRACTORS PROPOSAL AND DOES NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITY TO CORRECT THE SAME.
11. ADDITIONAL CLEARING AND GRUBBING BEYOND THE LIMITS SHOWN SHALL BE AT THE CONTRACTORS DISCRETION, SUBJECT TO THE OWNER'S APPROVAL, TO FACILITATE CONSTRUCTION.
12. THE AUGUSTA UTILITIES DEPARTMENT (706-821-1706) SHALL BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE DURING REGULAR HOURS (8:30 AM TO 5:00 PM, MONDAY THROUGH FRIDAY, EXCLUDING AUGUSTA, GA HOLIDAYS) BEFORE THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY.
13. A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD WITH THE DIRECTOR OF AUGUSTA UTILITIES DEPARTMENT OR HIS REPRESENTATIVE PRIOR TO BEGINNING CONSTRUCTION. THIS MEETING SHALL BE SCHEDULED WITH THE DEPARTMENT AT THE TIME THE NOTIFICATION OF WORK COMMENCEMENT IS GIVEN.
14. ALL SILT BARRIERS MUST BE PLACED IMMEDIATELY FOLLOWING CLEARING. NO GRADING SHALL BE DONE UNTIL SILT BARRIERS INSTALLATION IS COMPLETED.
15. ACCORDING TO THE FEMA FIRM PANEL NUMBERS 13245C0140G & 13245C0230G, NO PORTIONS OF THIS PROPERTY LIE WITHIN THE 100 YEAR FLOOD PLAIN.
16. THE EXISTENCE, ABSENCE, LOCATION AND ELEVATION OF UNDERGROUND UTILITIES ON THE PLANS ARE NOT BASED ON FIELD MARKS, ARE NOT GUARANTEED, AND SHALL BE INVESTIGATED, UNEARTHED IF NECESSARY, AND VERIFIED BY CONTRACTOR BEFORE BEGINNING CONSTRUCTION.
17. ALL UNDERGROUND UTILITIES SHALL BE FIELD LOCATED AND MARKED BEFORE BEGINNING CONSTRUCTION.
18. NO EXTRA PAYMENT WILL BE MADE FOR REPAIRS TO DAMAGE OF EXISTING UTILITIES.
19. CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES, ABOVE GROUND OR UNDERGROUND, POWER POLES, ETC.; CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH APPROPRIATE UTILITIES PRIOR TO OR DURING CONSTRUCTION.
20. THE FOLLOWING UTILITY OWNERS MAY HAVE FACILITIES WHICH CONFLICT WITH THE PROPOSED CONSTRUCTION ON THIS PROJECT:
GEORGIA POWER COMPANY KMC TELECOM
ATLANTA GAS LIGHT COMPANY AT&T
AUGUSTA UTILITIES -WATER & SEWER COMCAST
JEFFERSON EMC WOW
21. THE CONTRACTOR SHALL CONTACT THE UTILITIES PROTECTION INC. "CALL BEFORE YOU DIG" SERVICE, 811 IN ORDER TO LOCATE UTILITIES PRIOR TO STARTING ANY EXCAVATION OR CONSTRUCTION.
22. ALL KNOWN UTILITY FACILITIES ARE SHOWN SCHEMATICALLY IN PLANS, AND ARE NOT NECESSARILY ACCURATE IN LOCATION AS TO PLAN OR ELEVATION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD LOCATE ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION.





N. Max Hicks Water Plant
Reservoir Dam Improvements

Legend & Notes


DRAWN BY:	MAB
CHECKED BY:	RDS
APPROVED BY:	EAW
DATE:	APRIL 26, 2019
SCALE:	NO SCALE
JOB No.	2018-0102
DRAWING No.	



CRANSTON




G:\PROJECTS\2018-0102 - HICKS WATER PLANT DAM IMPROVEMENTS\AC-DRAWINGS\DWG\20180102_DRAWING 5/21/2023 2:28 PM



NOTE:
TOPOGRAPHIC INFORMATION FROM RICHMOND COUNTY, GEORGIA GIS.

PLAN
HORIZONTAL SCALE 1"=300'

300 150 0 300 600
SCALE IN FEET




GSWCC Georgia Storm Water Conservation Commission

Mitchell B Murchison
Level II Certified Design Professional



CERTIFICATION NUMBER: 000546276
ISSUED: 12/21/2022 EXPIRES: 12/21/2023

Mitchell M 6/9/2023

GEORGIA811
www.Georgia811.com



CRANSTON




REV #	DATE	DESCRIPTION
1	2/20/2020	FEE SAFE DAM COMMENTS

N. Max Hicks Water Plant
Reservoir Dam Improvements

Overall Existing Conditions

DRAWN BY: MAB
CHECKED BY: RDS
APPROVED BY: EAW
DATE: APRIL 26, 2019
SCALE: 1" = 300'
JOB No. 2018-0102
DRAWING No.

G:\PROJECTS\2018-0102 - HICKS WATER PLANT DAM IMPROVEMENTS\AC-DRAWINGS\CIVIL\20180102_PLAN.DWG 7/31/2023 10:15 AM



- LEGEND**
- ⊕ TEMPORARY BENCHMARK (BM)
 - ⊠ CONTROL POINT (CP)
 - ⊙ MONITORING WELL (MW)


NOTE:
TOPOGRAPHIC INFORMATION FROM RECORD DRAWINGS DATED
MAY 23, 2007 BY ROSS CONSULTING ENGINEERS, P.C.

PLAN
HORIZONTAL SCALE 1"=60'

60 30 0 60 120
SCALE IN FEET

APPROVED
STATE OF GEORGIA
DEPT. OF NATURAL RESOURCES
AUG 25 2025
Safe Dams Program
Environmental Protection Division
By: *[Signature]* P.E.

GSWCC Georgia State and Water
Conservation Commission
Mitchell B Murchison
Level II Certified Design Professional
CERTIFICATION NUMBER: 000046296
ISSUED: 12/25/2022 EXPIRES: 12/25/2025




GEORGIA811
www.Georgia811.com

N. Max Hicks Water Plant
Reservoir Dam Improvements

Site Plan

DRAWN BY: MAB
CHECKED BY: RDS
APPROVED BY: EAW
DATE: APRIL 26, 2019
SCALE: 1" = 60'
JOB No. 2018-0102
DRAWING No.

04



REV #	DATE	DESCRIPTION
3	7/28/2025	AUD CLEARING AREAS
2	5/25/2023	PREPARE FOR BIDDING
1	2/20/2020	PER SAFE DAM COMMENTS

N. Max Hicks Water Plant
Reservoir Dam Improvements

Site Plan

DRAWN BY: MAB
CHECKED BY: RDS
APPROVED BY: EAW
DATE: APRIL 26, 2019
SCALE: 1" = 60'
JOB No. 2018-0102
DRAWING No.

04

GENERAL EROSION CONTROL NOTES:

- ALL DISTURBED AREAS SHALL HAVE EROSION CONTROL PROVIDED IN ACCORDANCE WITH THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA , CURRENT EDITION.
- ALL EROSION CONTROL MEASURES SHALL COMPLY WITH THE STATE OF GEORGIA SOIL AND WATER CONSERVATION COMMISSION MANUAL FOR EROSION AND SEDIMENT CONTROL IN THE STATE OF GEORGIA , CURRENT EDITION.
- FULL COORDINATION SHALL BE MAINTAINED BETWEEN THE CONTRACTOR, DESIGN PROFESSIONAL, AND THE REGULATORY INSPECTOR REGARDING PROJECT SEQUENCE.
- THE NOTATION (XXX) AS SHOWN ON THE EROSION CONTROL PLAN SHEET(S) AND ON THE EROSION CONTROL DETAIL SHEET FOR THE EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES, REFERS TO THE GEORGIA UNIFORM CODING SYSTEM AS DETAILED IN THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA , CURRENT EDITION.
- GENERAL STATEMENT OF DESIGNED EROSION CONTROL SYSTEM:
 - NO SURFACE WATER FLOWS FROM DISTURBED AREA TO BE ALLOWED INTO THE STORM SEWER SYSTEM WITHOUT FIRST BEING FILTERED BY AN EFFECTIVE SEDIMENT ENTRAPMENT DEVICE.
 - SEDIMENT ENTRAPMENT DEVICES ARE TO BE MAINTAINED AT ALL POINTS WHERE SURFACE FLOWS FROM DISTURBED AREAS CAN LEAVE THE SITE. FLOWS ARE TO BE DIRECTED TO ENTRAPMENT DEVICES THROUGHOUT CONSTRUCTION ACTIVITIES.
- EROSION CONTROL MEASURES ARE TO BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES ON-SITE AND MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED. EROSION CONTROL MEASURES SHALL BE INSPECTED AT THE END OF EACH WORKING DAY AND AFTER EACH STORM EVENT TO ENSURE THAT ALL MEASURES ARE FUNCTIONING PROPERLY. ANY REPAIRS SHALL BE MADE BY THE CONTRACTOR.
- IN ADDITION TO THE NOTE ABOVE, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AT LEAST WEEKLY, AFTER EACH RAIN EVENT, AND REPAIRED AS NECESSARY THESE INSPECTIONS SHALL BE DOCUMENTED WITH COPIES SENT TO THE OWNER.
- EROSION AND SEDIMENT CONTROL DEVICES MUST BE INSTALLED AND INSPECTED PRIOR TO ANY LAND DISTURBANCE ON SITE. SILT BARRIER TO BE PLACED AS SHOWN AND/OR AS DIRECTED BY THE PROJECT ENGINEER AND/OR OWNER: BOARD OF COMMISSIONERS OF AUGUSTA, GEORGIA.
- THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES, PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES.
- EROSION AND SEDIMENTATION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- ANY DISTURBED AREA LEFT IDLE/EXPOSED FOR A PERIOD GREATER THAN 14-DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING; DISTURBED AREAS IDLE/EXPOSED 30-DAYS SHALL BE STABILIZED WITH PERMANENT VEGETATION.
- ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IF DETERMINED NECESSARY BY ON-SITE INSPECTION.
- THE CONTRACTOR SHALL COMPLETELY REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (I.E. SILT FENCE, SEDIMENT TRAPS, ETC...) AND TREE PROTECTION FENCING ONCE PERMANENT VEGETATION IS ESTABLISHED.
- THE CONTRACTOR IS RESPONSIBLE FOR MONITORING DOWNSTREAM CONDITIONS THROUGHOUT THE CONSTRUCTION PERIOD AND FOR CLEARING ANY DEBRIS AND SEDIMENT THAT IS CAUSED BY CONSTRUCTION ACTIVITIES.
- ALL DISTURBED AREAS SHALL BEST BE STABILIZED AS REQUIRED BY THESE PLANS BY THE SITEWORK CONTRACTOR AS SOON AS CONSTRUCTION PHASES PERMIT.
- WHEN HAND PLANTING, MULCH (HAY OR STRAW) SHOULD BE UNIFORMLY SPREAD OVER SEEDED AREA WITHIN 24-HOURS OF SEEDING.
- DURING UNSUITABLE GROWING SEASONS, MULCH WILL BE USED AS A TEMPORARY COVER (Ds1). ON SLOPES 4:1 OR STEEPER, MULCH WILL BE ANCHORED.
- SILT FENCE SHALL MEET THE MINIMUM REQUIREMENTS OF SECTION 171 OF THE STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION, STANDARD SPECIFICATIONS, CURRENT EDITION, AND/OR GEORGIA EPD "GREEN BOOK" AS AMENDED.
- SEDIMENT STORAGE MAINTENANCE INDICATORS MUST BE INSTALLED IN SEDIMENT STORAGE STRUCTURES, INDICATING THE 1/3 FULL VOLUME FOR RETROFITS AND TEMPORARY SEDIMENT BASINS, AND THE 1/2 FULL VOLUME FOR ALL OTHER SEDIMENT STORAGE STRUCTURES (I.E. CHECK DAMS, SILT FENCE, ETC...).
- ALL SEDIMENT STORAGE DEVICES ARE TO BE CONSTRUCTED COMPLETELY AND FULLY OPERATIONAL PRIOR TO ANY OTHER CONSTRUCTION OR GRADING.
- CONCENTRATED FLOW AREAS AND ALL SLOPES STEEPER THAN 2.5:1 WITH A HEIGHT OF TEN FEET OR GREATER SHALL BE STABILIZED WITH APPROPRIATE EROSION CONTROL MATTING AND BLANKETS.
- ALL PERMANENT GRADED EARTH SLOPES, EXCAVATION OR EMBANKMENT (CUT AND FILL), SHALL BE GRADED TO A MAXIMUM FINISHED SLOPE OF TWO (2) FEET HORIZONTAL TO ONE (1) FOOT VERTICAL (MAXIMUM SLOPE 2H:1V).
- ALL DISTURBED AREAS LEFT MULCHED AFTER 30-DAYS SHALL BE STABILIZED WITH TEMPORARY GRASSING.
- SEDIMENT SHALL NOT BE WASHED INTO INLETS. IT SHALL BE REMOVED FROM THE SEDIMENT TRAPS AND DISPOSED OF AND STABILIZED SO THAT IT WILL NOT ENTER THE INLETS.
- FAILURE TO INSTALL, OPERATE, OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE APPROVED EROSION CONTROL PLANS, I.E., MANDATORY STOP WORK ORDER.
- THE CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1-3" STONE, AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEAN-OUT OF ANY STRUCTURES USED TO TRAP SEDIMENT. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM A VEHICLE OR FROM THE SITE ONTO PUBLIC ROADWAY OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.

INITIAL PHASE (CLEARING & GRUBBING) NOTES:

- ALL STAGING AREAS, MATERIAL STORAGE AREAS, CONCRETE WASH-OUT AREAS, SHALL BE LOCATED AT SETBACK DISTANCES FROM DESIGNATED TREE PROTECTION AREAS AND/OR STREAM BUFFERS AS REQUIRED BY LOCAL AND STATE REGULATIONS.
- A COPY OF THE APPROVED LAND DISTURBANCE PLAN AND PERMIT SHALL BE PRESENT ON THE SITE AT ALL TIMES. POST ON DAY ONE.
- PRIOR TO COMMENCING LAND DISTURBING ACTIVITY, THE LIMITS OF LAND DISTURBANCE SHALL BE CLEARLY AND ACCURATELY DELINEATED WITH STAKES, RIBBONS, OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE ACTIVITY SHALL BE DEMARCATED FOR THE DURATION OF THE CONSTRUCTION ACTIVITY. NO LAND DISTURBANCE SHALL OCCUR OUTSIDE THE APPROVED LIMITS INDICATED ON THE APPROVED PLANS.
- PRIOR TO ANY OTHER CONSTRUCTION, A STABILIZED CONSTRUCTION EXIT (Co) SHALL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE OR ONTO ANY PUBLIC ROADWAY AS SHOWN ON THE PLANS.

LOCATION:
LATITUDE: 33.374483 N LONGITUDE: -81.992026
- IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION ENTRANCE/EXITS, ALL PERIMETER EROSION CONTROL AND STORMWATER MANAGEMENT DEVICES SHALL BE INSTALLED AS SHOWN ON THE INITIAL PHASE OF THE EROSION CONTROL PLAN.
- SILT FENCE OR APPROVED EQUAL SHALL BE INSTALLED AT THE PERIMETER OF THE DISTURBED AREA OR AS SHOWN ON THE PLAN. SILT SHOULD BE REMOVED WHEN ACCUMULATION REACHES HALF THE HEIGHT OF THE BARRIER. THE PERIMETER SILT FENCE SHOULD BE INSPECTED DAILY FOR ANY FAILURES. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.
- INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED ON ALL EXISTING STORM STRUCTURES AS SHOWN ON THE PLAN.
- TREE PROTECTION FENCING AND STREAM BUFFER LIMITS SHOULD BE INSTALLED PRIOR TO THE START OF ANY LAND DISTURBING ACTIVITY AND MAINTAINED UNTIL FINAL LANDSCAPE IS INSTALLED. THE TREE PROTECTION FENCING SHOULD BE INSPECTED DAILY. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.
- AFTER INSTALLATION OF INITIAL EROSION CONTROL MEASURES, THE SITE CONTRACTOR SHALL SCHEDULE AN INSPECTION BY THE PROJECT DESIGN PROFESSIONAL WITHIN 7 DAYS AFTER INSTALLATION. NO OTHER CONSTRUCTION ACTIVITIES SHALL OCCUR UNTIL THE PROJECT PROFESSIONAL APPROVES THE INSTALLATION OF SAID EROSION MEASURES. IF UNFORESEEN CONDITIONS EXIST IN THE FIELD THAT WARRANT ADDITIONAL EROSION CONTROL MEASURES, THE CONTRACTOR MUST CONSTRUCT ANY ADDITIONAL EROSION CONTROL DEVICES DEEMED NECESSARY BY THE SITE INSPECTION WITH CONSULTATION WITH THE DESIGN PROFESSIONAL.
- AFTER APPROVAL OF THE INITIAL EROSION CONTROL INSTALLATION, THE CONTRACTOR MAY PROCEED WITH CLEARING AND GRUBBING ACTIVITIES. AS CLEARING PERMITS, THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SEDIMENT STORAGE DEVICES AS SHOWN ON THE INITIAL PHASE PLAN TO CONTROL EROSION AND STORMWATER RUNOFF.
- INITIAL PHASE BMPs UTILIZED IN THIS PLAN(S) ARE AS FOLLOWS:
Co, Fr, Sd1-S, RL-P

INTERMEDIATE PHASE (GRADING & TEMPORARY VEGETATION) NOTES:

- MAINTAIN PREVIOUSLY INSTALLED BMPs.
- SCHEDULING AND PERFORMANCE TO ENSURE THAT LAND STRIPPED OF ITS NATURAL GROUND COVER IS EXPOSED ONLY IN SMALL QUANTITIES, AND THEREFORE LIMITED DURATIONS, BEFORE PERMANENT EROSION PROTECTION IS ESTABLISHED.
- GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION AND SEDIMENTATION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE DESIGN PROFESSIONAL IMMEDIATELY.
- THE SILT FENCE SHALL BE MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES HALF OF THE HEIGHT OF THE BARRIER.
- SILT FENCE SHALL BE PLACED AT THE TOE OF ALL DIRT STOCK PILE AREAS.
- AFTER PRELIMINARY CLEARING AND GRADING ACTIVITIES, THE CONTRACTOR SHALL CONSTRUCT ALL SEDIMENT ENTRAPMENT DEVICES AS SHOWN ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN THE DEVICES UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT WHEN IT REACHES THE CLEAN-OUT ELEVATION SHOWN ON THE PLANS.
- SEDIMENT AND EROSION CONTROL MEASURES MUST BE CHECKED WEEKLY AND AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF OF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF NEW CHANNELS HAVE DEVELOPED.
- INTERMEDIATE PHASE BMPs UTILIZED ON THIS PLAN(S) ARE AS FOLLOWS:
Du, Ds2, Ss-RECP, Ss, Su

FINAL PHASE (STORMWATER MANAGEMENT & PERMANENT VEGETATION) NOTES:

- THE CONTRACTOR SHALL MAINTAIN ALL SEDIMENT DEVICES AND EROSION CONTROL MEASURES UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT OF EACH DEVICE WHEN IT REACHES THE REQUIRED CLEAN-OUT ELEVATION SHOWN ON THE PLANS.
- AFTER CURBING AND PAVEMENT HAS BEEN INSTALLED, ALL INLET SEDIMENT TRAPS ON THE EXISTING INLETS SHALL BE REMOVED AND REPLACED WITH CURB FILTER INLET PROTECTION.
- FINAL STABILIZATION OF PERMANENT GRASS MUST MEET 100% COVERAGE, 70% DENSITY RULE.
- FINAL PHASE BMPs UTILIZED ON THIS PLAN(S) ARE AS FOLLOWS:
Ds3

NOTE:
THESE ARE STANDARD NOTES PROVIDED BY THE LOCAL ISSUING AUTHORITY AND MODIFIED BY THE DESIGN PROFESSIONAL.

GRASSING:


- APRIL 15 - SEPTEMBER 15
 - AREA "A" - WEEPING LOVEGRASS, 40 LBS./ACRE
 - AREA "B" - HULLED COMMON BERMUDA, 40-45 LBS./ACRE
- SEPTEMBER 15 - APRIL 15, AVRUZZI RYE, 200 LBS./ACRE
- FERTILIZER GRADE WILL BE A COMMERCIAL 10-10-10 INCORPORATED INTO THE SOIL AT 1000 LBS./ACRE, ALSO 1500 LBS. DOLOMITIC LIME.
- NOT LESS THAN 30 DAYS AFTER SEEDING, APPLY AMMONIUM NITRATE (NOT LESS THAN 20% NITRATE) AT A RATE EQUAL TO 60 LBS. OF AVAILABLE NITROGEN /ACRE. APPLICATION BETWEEN JUNE THRU AUGUST.
- ALL SEEDED AREAS WILL BE MULCHED WITH STRAW OR HAY MULCH AT A RATE OF 2.5 TONS/ACRE.
- FOR ALL DATES NOT COVERED UNDER THE GRASSING SCHEDULE THE DISTURBED SOIL SHALL BE TEMPORARILY STABILIZED USING POLYACRYLAMIDE.

GRASSING:

- ONSITE DRAINAGE BASIN = 9.62 ACRES (PORTION OF BASIN A IS OFFSITE)
- OFFSITE DRAINAGE BASIN = 1.21 ACRES
- CONTRACTOR TO ENSURE THAT EXISTING ON SITE VEGETATION OUTSIDE THE LIMITS OF CONSTRUCTION IS PRESERVED AND THAT ALL DISTURBED PORTIONS OF THE SITE ARE STABILIZED.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- NO WATERS OF THE STATE ARE IMPACTED ON THIS PROJECT.
- RECEIVING STREAM IS UNNAMED TRIBUTARY TO BUTLER CREEK. SHEET 01 OF 12 ON PLANS

THE PRIMARY PERMITTEE SHALL PROVIDE A COPY OF THE APPROVED EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN AND ANY SUBSEQUENT REVISIONS TO THE PLAN TO EACH SECONDARY PERMITTEE.

NAME	ADDRESS	PLANS RECIEVED BY/DATE



MONITORING POINTS

MONITORING POINT LOCATION IS SHOWN ABOVE:

- DOWNSTREAM MONITORING POINT AT OUTFALL OF 60" RCP FROM SEDIMENT POND

STORMWATER CALCULATIONS:


- REQUIRED STORMWATER STORAGE = 0 CY (AS DETERMINED BY LOCAL ORDINANCE)
- REQUIRED SEDIMENT STORAGE = 361 CY (67 CY/ACRE x 5.39 ACRES DISTURBED AREA)
- TOTAL REQUIRED STORAGE = 0 CY + 361 CY = 361 CY
- AVAILABLE STORAGE = 834 CY
- IS THE AVAILABLE STORAGE (X.XX CY) GREATER THAN STORAGE REQUIRED (361 CY)?
☒ YES ☐ NO

SEDIMENT STORAGE:

REQUIRED: 5.39 ACRES x 67 CY/ACRE = 361 CY
PROVIDED BY EX SEDIMENT BASIN:
THE VOLUME BETWEEN THE BOTTOM OF THE EXISTING SEDIMENT POND AND THE WEIR ELEVATION AT THE EXISTING RETROFIT IS APPROXIMATELY 834 CY.

APPROXIMATE START DATE: JUNE 1, 2019
APPROXIMATE FINISH DATE: AUGUST 30, 2019

WEEKS OF CONSTRUCTIONS ACTIVITIES



- NOTES:
- ALL DISTURBED AREAS NOT INTENDED FOR PAVING SHALL BE STABILIZED USING TEMPORARY MEASURES Ds2 AND PERMANENT MEASURES Ds3.

SITE SOIL TYPE	
SOIL MAP SYMBOL	SOIL NAME
AgC	AILEY LOAMY SAND, 2 TO 6 PERCENT SLOPES
DgA	DOGUE FINE SANDY LOAM, 6 TO 3 PERCENT SLOPES
DsA	DOTHAN LOAMY SAND, 6 TO 2 PERCENT SLOPES
DsB	DOTHAN LOAMY SAND, 3 TO 5 PERCENT SLOPES
FmB	FUQUAY LOAMY SAND, 1 TO 5 PERCENT SLOPES
GmA	GOLDSBORO LOAMY SAND
LmC	LUCY LOAMY SAND, 5 TO 8 PERCENT SLOPES
Ra	RAINS LOAMY SAND
Rr	ROANOKE LOAM
TwB	TROUP FINE SAND, 1 TO 5 PERCENT SLOPES
TwC	TROUP FINE SAND, 5 TO 10 PERCENT SLOPES
TwD	TROUP FINE SAND, 10 TO 17 PERCENT SLOPES
Us	UDBORTHENS, SANDY AND LOAMY
VaC	VAUCLUSE-AILEY COMPLEX, 5 TO 8 PERCENT SLOPES
VaD	VAUCLUSE-AILEY COMPLEX, 8 TO 17 PERCENT SLOPES

NTU VALUE: Δ50 (THIS IS FOR UPSTREAM AND DOWNSTREAM MONITORING IN WARM WATER STREAMS)

SITE SIZE: 10.83 ACRES
DRAINAGE AREA: 0.01 SQUARE MILES




24-HOUR LOCAL ES&PC CONTACT:

NAME: AUD DISPATCH
PHONE: 706-842-3060
EMAIL: CHENDRIX@AUGUSTA.GOV

N. Max Hicks Water Plant
Reservoir Dam Improvements



Erosion Control Notes

DRAWN BY: MAB
CHECKED BY: RDS
APPROVED BY: EAW
DATE: APRIL 26, 2019
SCALE: AS SHOWN
JOB No. 2018-0102
DRAWING No.




Intermediate Erosion Control Plan

09




GEORGIA811
www.Georgia811.com


\\projects\2018-0102 - Hicks Water Plant Dam Improvements\AC-DRAWINGS\Civil\20180102_DTLS.DWG 5/31/2023 2:30 PM



PERFORATED HALF-ROUND PIPE
WITH STONE FILTER
N.T.S. **Rt-P**




SIDE VIEW



FRONT VIEW

- NOTES:
1. USE 36" APPROVED FABRIC, WITH OAK OR STEEL POSTS.
 2. P-FACTOR MUST BE LESS THAN 0.045 IAW MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA, LATEST EDITION.
 3. FOR WOOD POSTS, CONNECT WITH A MINIMUM OF 5 EACH, 7 GAUGE STAPLES 3/4" WIDE AND 1/2" LONG, OR OTHER APPROVED METHOD.
 4. AT OVERLAPS, USE 18" MINIMUM OR WRAP ENDS TOGETHER AROUND A SINGLE POST TO FORM A CONTINUOUS BARRIER.
 5. FOR DOUBLE ROWS, SET FENCES 3 FEET APART.
 6. CONTRACTOR MAY USE "C-POP" SILT FENCE IN ACCORDANCE WITH GA. DOT SPECIFICATIONS, IN LIEU OF TYPE-C SILT FENCE.

SILT FENCE - TYPE C
N.T.S. **Sd1-S**




ISOMETRIC VIEW

- NOTES:
1. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS & GRASS. MATS/ BLANKETS SHALL HAVE GOOD SOIL CONTACT.
 2. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS.
 3. LAY BLANKETS LOOSELY & STAKE OR STAPLE TO MAINTAIN CONTACT WITH THE SOIL. DO NOT STRETCH.


SLOPE STABILIZATION
N.T.S. **Ss-RECP**

SURFACE ROUGHENING
(GROOVING SLOPES) **Su**

- CONDITIONS:
1. ALL SLOPES STEEPER THAN 3:1 REQUIRE SURFACE ROUGHENING.
 2. SLOPES LESS THAN 3:1 SHOULD HAVE THE SOIL SURFACE LIGHTLY ROUGHENED AND LOOSENED TO A DEPTH OF 2"-4" PRIOR TO SEEDING.
 3. AREAS WHICH HAVE BEEN GRADED AND WILL NOT BE STABILIZED IMMEDIATELY MAY BE ROUGHENED TO REDUCE RUNOFF VELOCITY UNTIL SEEDING TAKES PLACE.
 4. SLOPES WITH A STABLE ROCK FACE DO NOT REQUIRE ROUGHENING OR STABILIZATION.



CRUSHED STONE
CONSTRUCTION OUTLET
N.T.S. **Co**



STONE FILTER RING
N.T.S. **Fr**

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Co	CONSTRUCTION EXIT			A CRUSHED STONE PAD LOCATED AT THE CONSTRUCTION SITE EXIT TO PROVIDE A PLACE FOR REMOVING MUD FROM TIRES THEREBY PROTECTING PUBLIC STREETS.
Fr	FILTER RING			A TEMPORARY STONE BARRIER CONSTRUCTED AT STORM INLETS AND POND OUTLETS.
Rt	RETROFITTING			A DEVICE OR STRUCTURE PLACED IN FRONT OF A PERMANENT STORMWATER DETENTION POND OUTLET STRUCTURE TO SERVE AS A TEMPORARY SEDIMENT FILTER.
Sd1	SEDIMENT BARRIER			A BARRIER TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. IT MAY BE SANDBAGS, BALES OF STRAW OR STRAW, BRUSH, LOSS AND POLES, GRAVEL OR A SILT FENCE.
Su	SURFACE ROUGHENING			A ROUGH SOIL SURFACE WITH HORIZONTAL DEPRESSIONS ON A CONTOUR OR SLOPES LEFT IN A ROUGHENED CONDITION AFTER GRADING.

VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds2	DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING)			ESTABLISHING A TEMPORARY VEGETATIVE COVER WITH FAST GROWING SEEDINGS ON DISTURBED AREAS.
Ds3	DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION)			ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUBS, VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREA.
Du	DUST CONTROL ON DISTURBED AREAS			CONTROLLING SURFACE AND AIR MOVEMENT OF DUST ON CONSTRUCTION SITE, ROADWAYS AND SIMILAR SITES.
Ss-RECP	SLOPE STABILIZATION			A PROTECTIVE COVERING USED TO PREVENT EROSION AND ESTABLISH TEMPORARY OR PERMANENT VEGETATION ON STEEP SLOPES, SHORE LINES, OR CHANNELS.

GSWCC
Georgia Soil and Water
Conservation Commission
Mitchell B Murchison
Level II Certified Design Professional
CERTIFICATION NUMBER 000046296
EXPIRATION DATE 12/31/2023

6/9/2023
GEORGIA811
www.Georgia811.com


CRANSTON

GEORGIA
REGISTERED
NO. PE031775
PROFESSIONAL
ENGINEER
SCOTT WILLIAMS


GEORGIA
REGISTERED
NO. 11971
PROFESSIONAL
ENGINEER
EDWARD A. WHITEHURST, JR.
4-26-19

N. Max Hicks Water Plant
Reservoir Dam Improvements
Erosion Control Details


DRAWN BY: MAB
CHECKED BY: RDS
APPROVED BY: EAW
DATE: APRIL 26, 2019
SCALE: AS SHOWN
JOB No. 2018-0102
DRAWING No.



EXISTING DAM EMBANKMENT SECTION
N.T.S.



EXISTING DAM EMBANKMENT WITH BACKSLOPE SECTION
N.T.S.



EXISTING RETROFIT
N.T.S.

GEORGIA REGISTERED ENGINEER
NO. PE031775
PROFESSIONAL
9/29/23

GEORGIA REGISTERED ENGINEER
NO. 11971
PROFESSIONAL
9/29/23

REV #	DATE	DESCRIPTION
2	9/28/2023	ADD SEQUENCE OF CONSTRUCTION
1	2/20/2020	PER SAFE DAM COMMENTS


N. Max Hicks Water Plant
Reservoir Dam Improvements

Miscellaneous Details

DRAWN BY: MAB
CHECKED BY: RDS
APPROVED BY: EAW
DATE: APRIL 26, 2019
SCALE: AS SHOWN
JOB No. 2018-0102
DRAWING No.

GSWCC
Mitchell B Murchison
Level II Certified Design Professional
CERTIFICATION NUMBER 000046396
ISSUED 12/25/2022 EXPIRES 12/25/2025

GEORGIA811
www.Georgia811.com



VICINITY MAP
N.T.S.

Sheet Index	
Sheet Number	Sheet Title
C100	Cover
C200	Notes
C300	Site Plan
C400	Sections
C401	Sections & Details
C600	Erosion Control Notes
C601	Erosion Control Notes
C602	Erosion Control Notes
C603	Initial Erosion Control Plan
C604	Intermediate Erosion Control Plan
C605	Final Erosion Control Plan
C606	Erosion Control Details

BENCHMARK DATA			
NAME	NORTHING	EASTING	ELEVATION
BM-1	1262955.387	696590.381	469.85 (NAVD88)



CONSTRUCTION PLANS FOR

HIGHLAND AVENUE WATER TREATMENT PLANT RESERVOIR DAM #1 EAST & DAM #2 WEST IMPROVEMENTS

PREPARED FOR

**BOARD OF COMMISSIONERS OF
AUGUSTA, GEORGIA**

535 TELFAIR STREET, SUITE 220
AUGUSTA, GA 30901



LOCATION MAP
N.T.S.

- PROJECT DATA:**
1. ACREAGE OF PROPERTY: 48.05 ACRES
 2. ACREAGE OF DEVELOPMENT: 5.6 ACRES
 3. OWNER/DEVELOPER:
BOARD OF COMMISSIONERS OF AUGUSTA, GEORGIA
452 WALKER STREET, SUITE 200
AUGUSTA, 30901
PHONE: 706-312-4153
 - 24 HOUR CONTACT:
NAME: AUD DISPATCH
PHONE: 706-842-3060
 4. TAX MAP & PARCEL NUMBERS: 043-2-153-00-0
 5. ZONING: R-1B
 6. DRAINAGE AREA THIS PROJECT: 5.6 ACRES
 7. IMPERVIOUS AREA:
EXISTING: 0 ACRES
PROPOSED: 0 ACRES
 8. PERVIOUS AREA:
EXISTING: 5.6 ACRES
PROPOSED: 5.6 ACRES
 9. RECEIVING STREAM: VARIOUS
 10. ULTIMATE STREAM: SAVANNAH RIVER

PREPARED BY





ENGINEERS - PLANNERS - SURVEYORS

452 Ellis Street, Augusta, Georgia 30901
Telephone 706-722-1588
CranstonEngineering.com

NOVEMBER 26, 2019

LAST REV. MARCH 12, 2021



2018-0273
C100

GS:\PROJECTS\2018-2019-0273 - Highland Avenue Water Plant Reservoir Dam\AC-DRAWINGS\Civil\2018-0273-DTL-01.DWG 3/21/2023 2:47 PM

GENERAL NOTES:

1. ALL WORK TO BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE STANDARD SPECIFICATIONS OF THE AUGUSTA UTILITIES DEPARTMENT, AND THE PROJECT SPECIFICATIONS.
2. COORDINATE ROAD CLOSINGS AND DETOURS WITH THE AUGUSTA-RICHMOND COUNTY PUBLIC WORKS & ENGINEERING DEPARTMENT (706) 821-1706.
3. CERTIFIED FLAGGERS AND/OR ARROW BOARDS WILL BE REQUIRED TO MAINTAIN TRAFFIC CONTROL WHILE WORKING WITHIN THE LIMITS OF PUBLIC OR PRIVATE ROADWAYS.
4. DATE OF SURVEY – DATA OBTAINED FROM ORIGINAL CONSTRUCTION PLANS; NO SEPARATE SURVEY MADE.
5. THE DATA, TOGETHER WITH ALL OTHER INFORMATION SHOWN ON THESE PLANS, OR INDICATED IN ANY WAY THEREBY, WHETHER BY DRAWINGS OR NOTES OR ANY OTHER MANNER, ARE BASED UPON FIELD INVESTIGATIONS AND ARE BELIEVED TO BE INDICATIVE OF ACTUAL CONDITIONS. HOWEVER, THE SAME ARE SHOWN AS INFORMATION ONLY AND ARE NOT GUARANTEED.
6. THE CONTRACTOR WILL IMMEDIATELY NOTIFY THE OWNER IN THE EVENT THAT PREVIOUSLY UNKNOWN HISTORICAL OR ARCHEOLOGICAL SITES ARE DISCOVERED DURING CONSTRUCTION. NO ADDITIONAL WORK IN SUCH AREAS WILL BE ALLOWED UNTIL AUTHORIZED.
7. ALL STRUCTURES, TREES AND SHRUBS WHICH ARE WITHIN THE DESIGNATED CONSTRUCTION AREA, BUT OUTSIDE THE LIMITS OF CONSTRUCTION SHALL NOT BE DISTURBED UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER.
7. CONTRACTOR IS TO CLEAN ALL STORM WATER INLETS AND PIPE AT THE COMPLETION OF CONSTRUCTION TO REMOVE ANY SILT AND DEBRIS. THE CLEANING OF DROP INLETS, CULVERTS, AND PIPES (EXISTING AND PROPOSED) SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT, NO ADDITIONAL PAYMENT WILL BE MADE THEREFOR.
8. UNSUITABLE AND SURPLUS EXCAVATION MATERIAL NOT REQUIRED FOR FILL MAY BE DISPOSED IN ONSITE WASTE OR SPOIL AREAS. CONTRACTOR TO OBTAIN APPROVAL OF ENGINEER FOR EXACT WASTE DISPOSAL AREA.
9. DISTURBANCES TO ANY SURVEY MARKERS OR MONUMENTS REQUIRES RE-ESTABLISHMENT BY A LICENSED SURVEYOR AT THE CONTRACTOR'S EXPENSE.
10. ANY DISCREPANCIES, ERRORS, OR OMISSIONS DISCOVERED ON THE PLANS OR IN THE SPECIFICATIONS SHOULD BE NOTED ON THE CONTRACTORS PROPOSAL AND DOES NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITY TO CORRECT THE SAME.
11. ADDITIONAL CLEARING AND GRUBBING BEYOND THE LIMITS SHOWN SHALL BE AT THE CONTRACTORS DISCRETION, SUBJECT TO THE OWNER'S APPROVAL, TO FACILITATE CONSTRUCTION.
12. THE AUGUSTA UTILITIES DEPARTMENT (706-821-1706) SHALL BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE DURING REGULAR HOURS (8:30 AM TO 5:00 PM, MONDAY THROUGH FRIDAY, EXCLUDING AUGUSTA, GA HOLIDAYS) BEFORE THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY.
13. A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD WITH THE DIRECTOR OF AUGUSTA UTILITIES DEPARTMENT OR HIS REPRESENTATIVE PRIOR TO BEGINNING CONSTRUCTION. THIS MEETING SHALL BE SCHEDULED WITH THE DEPARTMENT AT THE TIME THE NOTIFICATION OF WORK COMMENCEMENT IS GIVEN.
14. ALL SILT BARRIERS MUST BE PLACED IMMEDIATELY FOLLOWING CLEARING. NO GRADING SHALL BE DONE UNTIL SILT BARRIERS INSTALLATION IS COMPLETED.
15. ACCORDING TO THE FEMA FIRM PANEL NUMBER 13245C0110G, NO PORTIONS OF THIS PROPERTY LIE WITHIN THE 100 YEAR FLOOD PLAIN.
16. THE EXISTENCE, ABSENCE, LOCATION AND ELEVATION OF UNDERGROUND UTILITIES ON THE PLANS ARE NOT BASED ON FIELD MARKS, ARE NOT GUARANTEED, AND SHALL BE INVESTIGATED, UNEARTHED IF NECESSARY, AND VERIFIED BY CONTRACTOR BEFORE BEGINNING CONSTRUCTION.
17. ALL UNDERGROUND UTILITIES SHALL BE FIELD LOCATED AND MARKED BEFORE BEGINNING CONSTRUCTION.
18. NO EXTRA PAYMENT WILL BE MADE FOR REPAIRS TO DAMAGE OF EXISTING UTILITIES.
19. CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES, ABOVE GROUND OR UNDERGROUND, POWER POLES, ETC.; CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH APPROPRIATE UTILITIES PRIOR TO OR DURING CONSTRUCTION.
20. THE FOLLOWING UTILITY OWNERS MAY HAVE FACILITIES WHICH CONFLICT WITH THE PROPOSED CONSTRUCTION ON THIS PROJECT:

GEORGIA POWER COMPANY

ATLANTA GAS LIGHT COMPANY

AUGUSTA UTILITIES –WATER & SEWER


JEFFERSON EMC

KMC TELECOM


AT&T

COMCAST

WOW
21. THE CONTRACTOR SHALL CONTACT THE UTILITIES PROTECTION INC: "CALL BEFORE YOU DIG" SERVICE, 811 IN ORDER TO LOCATE UTILITIES PRIOR TO STARTING ANY EXCAVATION OR CONSTRUCTION.
22. ALL KNOWN UTILITY FACILITIES ARE SHOWN SCHEMATICALLY IN PLANS, AND ARE NOT NECESSARILY ACCURATE IN LOCATION AS TO PLAN OR ELEVATION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD LOCATE ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION.
23. USE SIKADUR-51 NS, NON-SAGGING, FLEXIBLE JOINT SEALER BY SIKA, USA TO SEAL CRACKS IN CONCRETE LINER AND TO SEAL ANY LEAKS FOUND IN MANHOLES.



Know what's below.
Call before you dig.



ENGINEERS - PLANNERS - SURVEYORS
452 Ellis Street, Augusta, Georgia 30901
Telephone 706-722-1588
CranstonEngineering.com




REV #	DATE	DESCRIPTION
1	3/12/2021	ADD NOTE 23

Highland Avenue Water Treatment Plant Reservoir Dam #1 East & Dam #2 West Improvements	Notes
--	-------

DRAWN BY:	MAB
CHECKED BY:	WPM
APPROVED BY:	EAW
DATE:	NOVEMBER 26, 2019
SCALE:	NO SCALE
JOB No.	2018-0273
DRAWING No.	

C200

GS PROJECTS 2018\2018-0273 - HIGHLAND AVENUE WATER PLANT RESERVOIR DAM VAC-DRAWINGS\DWG 2018-0273.PLAN_01.DWG 7/31/2025 10:19 AM



PLAN
HORIZONTAL SCALE 1"=60'

60 30 0 60 120
SCALE IN FEET

APPROVED
STATE OF GEORGIA
DEPT. OF NATURAL RESOURCES
AUG 25 2025
Safe Dams Program
Environmental Protection Division
By: [Signature] P.E.



GSWCC Georgia Soil and Water Conservation Commission
Mitchell B Murchison
Level II Certified Design Professional
CERTIFICATION NUMBER: 00004236
EXPIRES: 12/31/2025

GEORGIA811
Utilities Protection Center, Inc.
Know what's below.
Call before you dig.

Highland Avenue Water Treatment Plant Reservoir Dam #1 East & Dam #2 West Improvements


Site Plan

DRAWN BY: MAB
CHECKED BY: WPM
APPROVED BY: EAW
DATE: NOVEMBER 26, 2019
SCALE: 1" = 60'
JOB No. 2018-0273
DRAWING No. C300



REV #	DATE	DESCRIPTION
4	7/28/2025	MISC. REVISIONS
3	5/25/2023	PREPARE FOR BIDDING
2	3/12/2021	ADD PIEZOMETERS
1	7/30/2020	PER SAFE DAMS REVIEW

G:\PROJECTS\2018\2018-0273 - HIGHLAND AVENUE WATER PLANT RESERVOIR DAM\AC-DRAWINGS\CIVIL\2018-0273_XSEC_01.DWG 7/31/2025 10:17 AM



RECEIVED
AUG 08 2025
Georgia Environmental Protection Division
Watershed Protection Branch

AUG 25 2025
Safe Dams Program
Environmental Protection Division
By: [Signature] P.E.

GSWCC Georgia Solid and Waste
Construction Commission
Mitchell B Murchison
Level II Certified Design Professional
CERTIFICATION NUMBER 000046296
ISSUED: 12/28/2022 EXPIRES: 12/28/2025

GEORGIA811
Utilities Protection Center, Inc.
Know what's below.
Call before you dig.




Highland Avenue Water Treatment
Plant Reservoir Dam #1 East &
Dam #2 West Improvements

Sections


DRAWN BY: MAB
CHECKED BY: WPM
APPROVED BY: EAW
DATE: NOVEMBER 26, 2019
SCALE: 1" = 10'
JOB No. 2018-0273
DRAWING No.

C400


G:\PROJECTS\2018\2018-0273 - Highland Avenue Water Plant Reservoir Dam\AC-DRAWINGS\CIVIL\2018-0273_CDES_01.DWG 7/31/2025 10:21 AM



TYPICAL DAM EMBANKMENT REPAIR SECTION
N.T.S.




TYPICAL TREE AND VEGETATION REMOVAL DETAIL
N.T.S.



TYPICAL TREE REMOVAL - PROFILE VIEW
N.T.S.

- NOTES:
1. CUT THE TREE APPROXIMATELY TWO FEET ABOVE GROUND LEVEL, LEAVING A PROMINENT STUMP FOR USE IN THE ROOTBALL REMOVAL PROCESS.
 2. LOOSEN THE ROOTBALL BY PULLING THE STUMP FROM DIFFERENT DIRECTIONS AND THEN REMOVE THE ROOTBALL AND STUMP ALL TOGETHER. THE ROOTBALL CAN BE ESTIMATED, IN FEET, TO EXTEND 0.825 TIMES THE TRUNK DIAMETER (IN INCHES) FROM THE TREE. THE MAJOR ROOT SYSTEM CAN EXTENT CAN BE ESTIMATED (IN FEET) AS TWICE THE ROOTBALL EXTENT (IN FEET). (FOR EXAMPLE FOR A 16 INCH TRUNK DIAMETER ROOTBALL, WILL EXTEND APPROXIMATELY 10 FEET FROM THE TREE AND THE MAJOR ROOT SYSTEM WILL EXTEND 20').
 3. CLEAN THE ROOTBALL CAVITY TO REMOVE LOOSE SOIL AND THE REMAINING ROOT SYSTEM BY EXCAVATING AND UNDERCUTTING THE ROOTBALL CAVITY MAXIMUM 1:1 (HORIZONTAL AND VERTICAL) SIDE SLOPES AND A HORIZONTAL BOTTOM.
 4. INSPECT UNDERCUT AREA TO CONFIRM THAT ALL MAJOR ROOT SYSTEMS GREATER THAN ABOUT ONE-HALF IN IN DIAMETER HAVE BEEN REMOVED DURING THE UNDERCUTTING OPERATION.
 5. BACKFILL WITH EXCAVATED EMBANKMENT FILL OR SIMILAR SUITABLE MATERIAL AND COMPACT IN MAXIMUM LOOSE LIFTS OF EIGHT INCHES. COMPACT WITH MANUALLY OPERATED OR BACKHOE-MOUNTED COMPACTION EQUIPMENT. MATERIALS CONSIDERED UNSUITABLE FOR BACKFILLING INCLUDE TOPSOIL, ORGANIC MATTER, CONTAMINATED SOIL, CONSTRUCTION DEBRIS, PERISHABLE MATERIALS, SOFT/COMPRESSIBLE SOILS, AND ROCKS OR LUMPS OF CEMENTED SOIL OVER 2 INCHES IN MAXIMUM DIMENSION.
 6. ESTABLISH GRASS COVER (OR EROSION PROTECTION) ON ALL DISTURBED AREAS.



APPROVED
OF GEORGIA
AUG 25 2025
Safe Dams Program
Environmental Protection Division
By: Mitchell B. Murchison, P.E.

GSWCC
Mitchell B. Murchison
Level II Certified Design Professional
Certification Number: 000046790
Issued: 12/25/2022
Expires: 12/25/2025

GEORGIA811
Utilities Protection Center, Inc.
Know what's below.
Call before you dig.

RECEIVED
AUG 08 2025
Georgia Environmental Protection Division
Watershed Protection Branch

Highland Avenue Water Treatment
Plant Reservoir Dam #1 East &
Dam #2 West Improvements

Sections & Details

DRAWN BY: MAB
CHECKED BY: WPM
APPROVED BY: EAW
DATE: NOVEMBER 26, 2019
SCALE: NO SCALE
JOB No. 2018-0273
DRAWING No. C401

GEORGIA
Cranston
Engineering
Group
NO. PEF000151
CERTIFICATE OF AUTHORIZATION

GEORGIA
REGISTERED
ENGINEER
ELIJAH W. CRANSTON, JR.
NO. 11871
PROFESSIONAL
7/28/2025

GENERAL EROSION CONTROL NOTES:

- ALL DISTURBED AREAS SHALL HAVE EROSION CONTROL PROVIDED IN ACCORDANCE WITH THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA, CURRENT EDITION.
- ALL EROSION CONTROL MEASURES SHALL COMPLY WITH THE STATE OF GEORGIA SOIL AND WATER CONSERVATION COMMISSION MANUAL FOR EROSION AND SEDIMENT CONTROL IN THE STATE OF GEORGIA, CURRENT EDITION.
- FULL COORDINATION SHALL BE MAINTAINED BETWEEN THE CONTRACTOR, DESIGN PROFESSIONAL, AND THE REGULATORY INSPECTOR REGARDING PROJECT SEQUENCE.
- THE NOTATION (XXX) AS SHOWN ON THE EROSION CONTROL PLAN SHEET(S) AND ON THE EROSION CONTROL DETAIL SHEET FOR THE EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES, REFERS TO THE GEORGIA UNIFORM CODING SYSTEM AS DETAILED IN THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA, CURRENT EDITION.
- GENERAL STATEMENT OF DESIGNED EROSION CONTROL SYSTEM:
 - NO SURFACE WATER FLOWS FROM DISTURBED AREA TO BE ALLOWED INTO THE STORM SEWER SYSTEM WITHOUT FIRST BEING FILTERED BY AN EFFECTIVE SEDIMENT ENTRAPMENT DEVICE.
 - SEDIMENT ENTRAPMENT DEVICES ARE TO BE MAINTAINED AT ALL POINTS WHERE SURFACE FLOWS FROM DISTURBED AREAS CAN LEAVE THE SITE. FLOWS ARE TO BE DIRECTED TO ENTRAPMENT DEVICES THROUGHOUT CONSTRUCTION ACTIVITIES.
- EROSION CONTROL MEASURES ARE TO BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES ON-SITE AND MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED. EROSION CONTROL MEASURES SHALL BE INSPECTED AT THE END OF EACH WORKING DAY AND AFTER EACH STORM EVENT TO ENSURE THAT ALL MEASURES ARE FUNCTIONING PROPERLY. ANY REPAIRS SHALL BE MADE BY THE CONTRACTOR.
- IN ADDITION TO THE NOTE ABOVE, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AT LEAST WEEKLY, AFTER EACH RAIN EVENT, AND REPAIRED AS NECESSARY THESE INSPECTIONS SHALL BE DOCUMENTED WITH COPIES SENT TO THE OWNER.
- EROSION AND SEDIMENT CONTROL DEVICES MUST BE INSTALLED AND INSPECTED PRIOR TO ANY LAND DISTURBANCE ON SITE. SILT BARRIER TO BE PLACED AS SHOWN AND/OR AS DIRECTED BY THE PROJECT ENGINEER AND/OR OWNER: BOARD OF COMMISSIONERS OF AUGUSTA, GEORGIA.
- THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES, PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES.
- EROSION AND SEDIMENTATION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- ANY DISTURBED AREA LEFT IDLE/EXPOSED FOR A PERIOD GREATER THAN 14-DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING; DISTURBED AREAS IDLE/EXPOSED 30-DAYS SHALL BE STABILIZED WITH PERMANENT VEGETATION.
- ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IF DETERMINED NECESSARY BY ON-SITE INSPECTION.
- THE CONTRACTOR SHALL COMPLETELY REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (I.E. SILT FENCE, SEDIMENT TRAPS, ETC...) AND TREE PROTECTION FENCING ONCE PERMANENT VEGETATION IS ESTABLISHED.
- THE CONTRACTOR IS RESPONSIBLE FOR MONITORING DOWNSTREAM CONDITIONS THROUGHOUT THE CONSTRUCTION PERIOD AND FOR CLEARING ANY DEBRIS AND SEDIMENT THAT IS CAUSED BY CONSTRUCTION ACTIVITIES.
- ALL DISTURBED AREAS SHALL BEST BE STABILIZED AS REQUIRED BY THESE PLANS BY THE SITEWORK CONTRACTOR AS SOON AS CONSTRUCTION PHASES PERMIT.
- WHEN HAND PLANTING, MULCH (HAY OR STRAW) SHOULD BE UNIFORMLY SPREAD OVER SEEDED AREA WITHIN 24-HOURS OF SEEDING.
- DURING UNSUITABLE GROWING SEASONS, MULCH WILL BE USED AS A TEMPORARY COVER (Ds1). ON SLOPES 4:1 OR STEEPER, MULCH WILL BE ANCHORED.
- SILT FENCE SHALL MEET THE MINIMUM REQUIREMENTS OF SECTION 171 OF THE STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION, STANDARD SPECIFICATIONS, CURRENT EDITION, AND/OR GEORGIA EPD "GREEN BOOK" AS AMENDED.
- SEDIMENT STORAGE MAINTENANCE INDICATORS MUST BE INSTALLED IN SEDIMENT STORAGE STRUCTURES, INDICATING THE 1/3 FULL VOLUME FOR RETROFITS AND TEMPORARY SEDIMENT BASINS, AND THE 1/2 FULL VOLUME FOR ALL OTHER SEDIMENT STORAGE STRUCTURES (I.E. CHECK DAMS, SILT FENCE, ETC...).
- ALL SEDIMENT STORAGE DEVICES ARE TO BE CONSTRUCTED COMPLETELY AND FULLY OPERATIONAL PRIOR TO ANY OTHER CONSTRUCTION OR GRADING.
- CONCENTRATED FLOW AREAS AND ALL SLOPES STEEPER THAN 2.5:1 WITH A HEIGHT OF TEN FEET OR GREATER SHALL BE STABILIZED WITH APPROPRIATE EROSION CONTROL MATTING AND BLANKETS.
- ALL PERMANENT GRADED EARTH SLOPES, EXCAVATION OR EMBANKMENT (CUT AND FILL), SHALL BE GRADED TO A MAXIMUM FINISHED SLOPE OF TWO (2) FEET HORIZONTAL TO ONE (1) FOOT VERTICAL (MAXIMUM SLOPE 2H:1V).
- ALL DISTURBED AREAS LEFT MULCHED AFTER 30-DAYS SHALL BE STABILIZED WITH TEMPORARY GRASSING.
- SEDIMENT SHALL NOT BE WASHED INTO INLETS. IT SHALL BE REMOVED FROM THE SEDIMENT TRAPS AND DISPOSED OF AND STABILIZED SO THAT IT WILL NOT ENTER THE INLETS.
- FAILURE TO INSTALL, OPERATE, OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE APPROVED EROSION CONTROL PLANS, I.E., MANDATORY STOP WORK ORDER.
- THE CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1-3" STONE, AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEAN-OUT OF ANY STRUCTURES USED TO TRAP SEDIMENT. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM A VEHICLE OR FROM THE SITE ONTO PUBLIC ROADWAY OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.

INITIAL PHASE (CLEARING & GRUBBING) NOTES:

- ALL STAGING AREAS, MATERIAL STORAGE AREAS, CONCRETE WASH-OUT AREAS, SHALL BE LOCATED AT SETBACK DISTANCES FROM DESIGNATED TREE PROTECTION AREAS AND/OR STREAM BUFFERS AS REQUIRED BY LOCAL AND STATE REGULATIONS.
- A COPY OF THE APPROVED LAND DISTURBANCE PLAN AND PERMIT SHALL BE PRESENT ON THE SITE AT ALL TIMES. POST ON DAY ONE.
- PRIOR TO COMMENCING LAND DISTURBING ACTIVITY, THE LIMITS OF LAND DISTURBANCE SHALL BE CLEARLY AND ACCURATELY DELINEATED WITH STAKES, RIBBONS, OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE ACTIVITY SHALL BE DEMARCATED FOR THE DURATION OF THE CONSTRUCTION ACTIVITY. NO LAND DISTURBANCE SHALL OCCUR OUTSIDE THE APPROVED LIMITS INDICATED ON THE APPROVED PLANS.
- PRIOR TO ANY OTHER CONSTRUCTION, A STABILIZED CONSTRUCTION EXIT (Co) SHALL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE OR ONTO ANY PUBLIC ROADWAY AS SHOWN ON THE PLANS.

LOCATION:
LATITUDE: N33.473686 LONGITUDE: W82.031574
LATITUDE: N33.472024 LONGITUDE: W82.035473
- IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION ENTRANCE/EXITS, ALL PERIMETER EROSION CONTROL AND STORMWATER MANAGEMENT DEVICES SHALL BE INSTALLED AS SHOWN ON THE INITIAL PHASE OF THE EROSION CONTROL PLAN.
- SILT FENCE OR APPROVED EQUAL SHALL BE INSTALLED AT THE PERIMETER OF THE DISTURBED AREA OR AS SHOWN ON THE PLAN. SILT SHOULD BE REMOVED WHEN ACCUMULATION REACHES HALF THE HEIGHT OF THE BARRIER. THE PERIMETER SILT FENCE SHOULD BE INSPECTED DAILY FOR ANY FAILURES. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.
- INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED ON ALL EXISTING STORM STRUCTURES AS SHOWN ON THE PLAN.
- TREE PROTECTION FENCING AND STREAM BUFFER LIMITS SHOULD BE INSTALLED PRIOR TO THE START OF ANY LAND DISTURBING ACTIVITY AND MAINTAINED UNTIL FINAL LANDSCAPE IS INSTALLED. THE TREE PROTECTION FENCING SHOULD BE INSPECTED DAILY. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.
- AFTER INSTALLATION OF INITIAL EROSION CONTROL MEASURES, THE SITE CONTRACTOR SHALL SCHEDULE AN INSPECTION BY THE PROJECT DESIGN PROFESSIONAL WITHIN 7 DAYS AFTER INSTALLATION. NO OTHER CONSTRUCTION ACTIVITIES SHALL OCCUR UNTIL THE PROJECT PROFESSIONAL APPROVES THE INSTALLATION OF SAID EROSION MEASURES. IF UNFORESEEN CONDITIONS EXIST IN THE FIELD THAT WARRANT ADDITIONAL EROSION CONTROL MEASURES, THE CONTRACTOR MUST CONSTRUCT ANY ADDITIONAL EROSION CONTROL DEVICES DEEMED NECESSARY BY THE SITE INSPECTION WITH CONSULTATION WITH THE DESIGN PROFESSIONAL.
- AFTER APPROVAL OF THE INITIAL EROSION CONTROL INSTALLATION, THE CONTRACTOR MAY PROCEED WITH CLEARING AND GRUBBING ACTIVITIES. AS CLEARING PERMITS, THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SEDIMENT STORAGE DEVICES AS SHOWN ON THE INITIAL PHASE PLAN TO CONTROL EROSION AND STORMWATER RUNOFF.
- INITIAL PHASE BMPs UTILIZED IN THIS PLAN(S) ARE AS FOLLOWS:
Co, Sd1-S

INTERMEDIATE PHASE (GRADING & TEMPORARY VEGETATION) NOTES:

- MAINTAIN PREVIOUSLY INSTALLED BMPs.
- SCHEDULING AND PERFORMANCE TO ENSURE THAT LAND STRIPPED OF ITS NATURAL GROUND COVER IS EXPOSED ONLY IN SMALL QUANTITIES, AND THEREFORE LIMITED DURATIONS, BEFORE PERMANENT EROSION PROTECTION IS ESTABLISHED.
- GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION AND SEDIMENTATION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE DESIGN PROFESSIONAL IMMEDIATELY.
- THE SILT FENCE SHALL BE MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES HALF OF THE HEIGHT OF THE BARRIER.
- SILT FENCE SHALL BE PLACED AT THE TOE OF ALL DIRT STOCK PILE AREAS.
- AFTER PRELIMINARY CLEARING AND GRADING ACTIVITIES, THE CONTRACTOR SHALL CONSTRUCT ALL SEDIMENT ENTRAPMENT DEVICES AS SHOWN ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN THE DEVICES UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT WHEN IT REACHES THE CLEAN-OUT ELEVATION SHOWN ON THE PLANS.
- SEDIMENT AND EROSION CONTROL MEASURES MUST BE CHECKED WEEKLY AND AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF OF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF NEW CHANNELS HAVE DEVELOPED.
- INTERMEDIATE PHASE BMPs UTILIZED ON THIS PLAN(S) ARE AS FOLLOWS:
Du, Sr, Ss-RECP

FINAL PHASE (STORMWATER MANAGEMENT & PERMANENT VEGETATION) NOTES:

- THE CONTRACTOR SHALL MAINTAIN ALL SEDIMENT DEVICES AND EROSION CONTROL MEASURES UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT OF EACH DEVICE WHEN IT REACHES THE REQUIRED CLEAN-OUT ELEVATION SHOWN ON THE PLANS.
- AFTER CURBING AND PAVEMENT HAS BEEN INSTALLED, ALL INLET SEDIMENT TRAPS ON THE EXISTING INLETS SHALL BE REMOVED AND REPLACED WITH CURB FILTER INLET PROTECTION.
- FINAL STABILIZATION OF PERMANENT GRASS MUST MEET 100% COVERAGE, 70% DENSITY RULE.
- FINAL PHASE BMPs UTILIZED ON THIS PLAN(S) ARE AS FOLLOWS:
Ds3

GRASSING:

- SEPTEMBER 15 - FEBRUARY 15, A MIXTURE OF UNHULLED COMMON BERMUDA 6 LBS./ACRE AND RYE GRASS SEED 28 LBS./ACRE APPLIED SIMULTANEOUSLY.
- OCTOBER 1 - MARCH 1, UNHULLED COMMON BERMUDA 10 LBS./ACRE.
- APRIL 1 - JUNE 1, HULLED COMMON BERMUDA 10 LBS./ACRE.
- FERTILIZER GRADE WILL BE A COMMERCIAL 6-12-12 INCORPORATED INTO THE SOIL AT 1500 LBS./ACRE, ALSO 1500 LBS. DOLOMITIC LIME.
- NOT LESS THAN 30 DAYS AFTER SEEDING, APPLY AMMONIUM NITRATE (NOT LESS THAN 20% NITRATE) AT A RATE EQUAL TO 80 LBS. OF AVAILABLE NITROGEN /ACRE. APPLICATION BETWEEN JUNE THRU AUGUST.
- ALL SEEDED AREAS WILL BE MULCHED WITH STRAW OR HAY MULCH AT A RATE OF 2.5 TONS/ACRE.
- FOR ALL DATES NOT COVERED UNDER THE GRASSING SCHEDULE THE DISTURBED SOIL SHALL BE TEMPORARILY STABILIZED USING POLYACRYLAMIDE.

GENERAL INFORMATION:

- ONSITE DRAINAGE BASIN = 5.6 ACRES
- OFFSITE DRAINAGE BASIN = 0.0 ACRES
- CONTRACTOR TO ENSURE THAT EXISTING ON SITE VEGETATION OUTSIDE THE LIMITS OF CONSTRUCTION IS PRESERVED AND THAT ALL DISTURBED PORTIONS OF THE SITE ARE STABILIZED.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- NO WATERS OF THE STATE ARE IMPACTED ON THIS PROJECT.
- RECEIVING STREAM IS VARIOUS.

THE PRIMARY PERMITTEE SHALL PROVIDE A COPY OF THE APPROVED EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN AND ANY SUBSEQUENT REVISIONS TO THE PLAN TO EACH SECONDARY PERMITTEE.

STORMWATER CALCULATIONS:


- REQUIRED STORMWATER STORAGE = 0.00 CY (AS DETERMINED BY LOCAL ORDINANCE)
- REQUIRED SEDIMENT STORAGE = 262 CY (67 CY/ACRE x 3.9 ACRES DISTURBED AREA)
- TOTAL REQUIRED STORAGE = 0.00 CY + 262 CY = 262 CY
- AVAILABLE STORAGE = 470 CY
- IS THE AVAILABLE STORAGE (470 CY) GREATER THAN STORAGE REQUIRED (262 CY)?
☒ YES ☐ NO

SEDIMENT STORAGE:


REQUIRED: 3.9 ACRES x 67 CY/ACRE = 262 CY
PROVIDED BY SILT FENCE: AVERAGE HEIGHT = 1.25 FEET
AVERAGE DEPTH = 6.25 FEET
AREA = 3.90 SF
VOLUME = 12,695 CF = 470 CY

APPROXIMATE START DATE: ---
APPROXIMATE FINISH DATE: ---

MONTHS OF CONSTRUCTIONS ACTIVITIES



NOTES:
1. ALL DISTURBED AREAS NOT INTENDED FOR PAVING SHALL BE STABILIZED USING TEMPORARY MEASURES Ds2 AND PERMANENT MEASURES Ds3.



MONITORING PLAN & SOILS MAP


1"=200'

MONITORING POINTS

MONITORING POINT LOCATIONS ARE SHOWN ABOVE:

THERE ARE NO DISTINCT MONITORING POINTS AVAILABLE


NOTE:
THESE ARE STANDARD NOTES PROVIDED BY THE LOCAL ISSUING AUTHORITY AND MODIFIED BY THE DESIGN PROFESSIONAL.



24-HOUR LOCAL ES&PC CONTACT:

NAME: AUD DISPATCH
PHONE: 706-842-3060
EMAIL: 24 HOUR CONTACT EMAIL

CRANSTON




ENGINEERING

ENGINEERS - PLANNERS - SURVEYORS

452 Ellis Street, Augusta, Georgia 30901

Telephone 706-722-1588

CranstonEngineering.com



PER. SAFE DAMS OFFICE
PER. SAFE DAMS REVIEW
DATE


REV. #

Highland Avenue Water Treatment
Plant Reservoir Dam #1 East &
Dam #2 West Improvements

Erosion Control Notes

DRAWN BY: MAB
CHECKED BY: WPM
APPROVED BY: EAW
DATE: NOVEMBER 26, 2019
SCALE: AS SHOWN
JOB No. 2018-0273
DRAWING No.

C602



CRASTON



0
Y
Z
Z
U
U
Z
—
0
Z
U

ENGINEERS - PLANNERS - SURVEYORS

Telephone 706-722-1588

CranstonEngineering.com

CranstonEngineering.com

[illegible]


Highland Avenue Water Treatment Plant Reservoir Dam #1 East & Dam #2 West Improvements

Initial Erosion Control Plan

DRAWN BY:	MAB
CHECKED BY:	WPM
APPROVED BY:	EAW
DATE:	NOVEMBER 26, 2019
SCALE:	1" = 60'
JOB No.	2018-0273
DRAWING No.	



C603

G:\PROJECTS\2018-0273 - HIGHLAND AVENUE WATER PLANT RESERVOIR DAM\AC-DRAWINGS\CIVIL\2018-0273-PLAN-ESPC-01.DWG 5/21/2023 2:49 PM




PLAN
HORIZONTAL SCALE 1"=60'

60 30 0 60 120
SCALE IN FEET




CRANSTON
ENGINEERING
ENGINEERS - PLANNERS - SURVEYORS
452 Ellis Street, Augusta, Georgia 30901
Telephone 706-722-1586
Cranstonengineering.com




Highland Avenue Water Treatment
Plant Reservoir Dam #1 East &
Dam #2 West Improvements
Final Erosion Control Plan

DRAWN BY:	MAB
CHECKED BY:	WPM
APPROVED BY:	EAW
DATE:	NOVEMBER 26, 2019
SCALE:	1" = 60'
JOB No.	2018-0273
DRAWING No.	C605




- NOTES:
1. USE STEEL OR WOOD POSTS OR AS SPECIFIED BY THE EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN.
 2. HEIGHT (H) IS TO BE SHOWN ON THE EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN.

SILT FENCE - TYPE C
N.T.S. Sd1-S



STAIR STEPPING CUT SLOPES
N.T.S. Su




SLOPE STABILIZATION
N.T.S. Ss-RECP

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Co	CONSTRUCTION EXIT			A CRUSHED STONE PAD LOCATED AT THE CONSTRUCTION SITE EXIT TO PROVIDE A PLACE FOR REMOVING MUD FROM TIRES THEREBY PROTECTING PUBLIC STREETS.
Sd1	SEDIMENT BARRIER			A BARRIER TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. IT MAY BE SANDBAGS, BALES OF STRAW OR HAY, BRUSH, LOGS AND POLES, GRAVEL OR A SILT FENCE.
Su	SURFACE ROUGHENING			A ROUGH SOIL SURFACE WITH HORIZONTAL DEPRESSIONS ON A CONTOUR OR SLOPES LEFT IN A ROUGHENED CONDITION AFTER GRADING.

VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds2	DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING)			ESTABLISHING A TEMPORARY VEGETATIVE COVER WITH FAST GROWING SEEDINGS ON DISTURBED AREAS.
Ds3	DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION)			ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUBS, VINES, GRASSES, SOY, OR LEGUMES ON DISTURBED AREA.
Du	DUST CONTROL ON DISTURBED AREAS			CONTROLLING SURFACE AND AIR MOVEMENT OF DUST ON CONSTRUCTION SITE, ROADWAYS AND SIMILAR SITES.
Ss-RECP	SLOPE STABILIZATION			A PROTECTIVE COVERING USED TO PREVENT EROSION AND ESTABLISH TEMPORARY OR PERMANENT VEGETATION ON STEEP SLOPES, SHORE LINES, OR CHANNELS.



- NOTES:
1. AVOID LOCATING ON STEEP SLOPES OR AT CURVES ON PUBLIC ROADS.
 2. REMOVE ALL VEGETATION AND OTHER UNSUITABLE MATERIAL FROM THE FOUNDATION AREA, GRADE, AND CROWN FOR POSITIVE DRAINAGE.
 3. AGGREGATE SIZE SHALL BE IN ACCORDANCE WITH NATIONAL STONE ASSOCIATION R-2 (1.5"-3.5" STONE).
 4. GRAVEL PAD SHALL HAVE A MINIMUM THICKNESS OF 6".
 5. PAD WIDTH SHALL BE EQUAL FULL WIDTH AT ALL POINTS OF VEHICULAR EGRESS, BUT NO LESS THAN 20'.
 6. A DIVERSION RIDGE SHOULD BE CONSTRUCTED WHEN GRADE TOWARD PAVED AREA IS GREATER THAN 2%.
 7. INSTALL PIPE UNDER THE ENTRANCE IF NEEDED TO MAINTAIN DRAINAGE DITCHES.
 8. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN (DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE ENTRANCE TO A SEDIMENT CONTROL DEVICE).
 9. WASHRACKS AND/OR TIRE WASHERS MAY BE REQUIRED DEPENDING ON SCALE AND CIRCUMSTANCE. IF NECESSARY, WASHRACK DESIGN MAY CONSIST OF ANY MATERIAL SUITABLE FOR TRUCK TRAFFIC THAT REMOVE MUD AND DIRT.
 10. MAINTAIN AREA IN A WAY THAT PREVENTS TRACKING AND/OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

CRUSHED STONE
CONSTRUCTION OUTLET
N.T.S. Co

